

M.S.P. Mandal's
Deogiri Institute of Engineering & Management Studies, Chhatrapati Sambhajinagar
 Quotation Comparative for 5th Floor Lab Interior Work

Sr. No.	Name of the Item	Qty	Rate	Total
1	Providing and fixing machine cut mirror polished 18mm to 20mm thick telephone black/amba white/cat bary brown/ RBI red/ ocean Brown Granite Stone Partition with full moulding the edges etc. complete one side polish(granite sill patti to windwo	113.32		
2	Providing and fixing black kadappa stone as shelves 25mm.thick machine polished extending the polish upto 20cm width on lower side, rounding corners, laying in position jointing with bedding cement mortar 1:4 proportion curing etc complete	93.43		
3	Providing and fixing fabrication and erecting sturctural steel members of grade yst fy 250 for make TATA Or jindal or any other similar approved make for columns, beams, rafters, trusses, purlinc, frame for louvers, bracing staircase cage ladders, etc including provision of necessary erection bolts, nuts, washers, cleats, stiffeners, gussets base plate, fencing and all operations straighterning cutting, drilling, grinding, welding, painting scaffolding etc. complete including all necessary machinary and manpower for the complete work as directed. M.S. fabrication work	1,689.53		
4	Provdng and applying two coats of flat oil paints of approved color to the old stuctural steel work and iron work previously painted in building including scaffolding if nenessary cleaning and preparing the surfacce excluding primer coat etc complate oil paints to M.S. grill & fabrication work	342.35		
5	Civil work	1.00		
6	pre-laminated sheet 18mm	45.32		
7	plumbing work	1.00		
8	PUF panel	21.09		
9	door kit with installation	1.00		
Total Basic Amount				
18% GST On Basic Amount				
Grand Total (Including GST)				
Terms & Conditions :				